

UNIVERSAL INTERIORS

No.180, Medavakkam Main Road, Adambakkam, Chennai 88.

Contact: 98403 00603

Date : 06th Jul 2026

To, Mr. Ravindran - Mrs. Karpagam, Villa 11, Sathyam Builders, Ponmar, Chennai

We had discussed with you on 06th Jul 2026

Updated Quotation - Plywood with Laminate Finish

Details	Height	Width	No. of Unit	Total Area
Kitchen and Pooja Box Area - Wood Work - A				
1. Kitchen Bottom	3	16	1	48
2. Kitchen wall Box	2.6	16	1	41.6
3. Pooja Unit (Inner Folding Door)	8	3	1	24
Total area - Kitchen Box Area - Wood Work - A				113.6
GF & FF Bedroom Wardrobe's - Wood work -B				
1. GF Bedroom Wardrobe	9	3.5	1	31.5
2. MBR Wardrobe (Inner)	9	3.5	1	31.5
3. Master bedroom wardrobe	7	6.5	1	45.5
4. SBR Wardrobe	7	4	1	28
Total area - Bedroom Wardrobe - Wood Work - B				136.5
BR COT, Hall Area and Other Box Area - Wood Work - C				
1. Hall TV Unit	9	7	1	63
2. GF BR COT with Storage	6	5	1	30
3. MBR COT with Storage	6.5	5	1	32.5
4. SBR COT with Storage	6	5	1	30
5. GBR Dressing Table with Bottom box - Tilted	7	2	1	14
6. FF SBR Dressing Table with bottom box - Tilted	7	2	1	14
7. Kitchen Loft Box	2.6	26	1	67.6
8. Hall Wash basin Bottom box	2	2.5	1	5

9. FF Study table with Book Shelf	7	4	1	28
10. Washing mAchine Top box	3	2	1	6
11. Shoe Rack	4	3	1	12
Total area - Hall Box Area - Wood Work - C				302.1
FF Study Room and Other Bedroom Area - Wood Work - D				
1. Study Room partition	7	4	1	28
2. Staircase Bottom Inverter Area	3	2	1	6
3. Small Tv unit panel with Ledge	4	4	1	16
4. Stair case Wall Panel	9	3.5	1	31.5
5. Panel with Mirror	6	2	1	12
6. Master bedroom Loft	2.6	10	1	26
7. Tv unit Wall panel	6	5	1	30
8. SBR bedroom Loft	2.6	10	1	26
9. Tv unit Wall panel	4	4	1	16
10. MBR Balcony panel	10	5	1	50
11. SBR Balcony panel	10	5	1	50
12. Entrance Panel (Near Staircase)	7	4	1	28
13. Kitchen Folding Table	4	2	1	8
Total area - Other Box Work - Wood Work - D				327.5
False Ceiling Work				
1. Hall Area	18	13	1.5	351
2. GF Bedroom	10	10	1	100
3. Kitchen	10	10	1	100
4. Study Room	10	10	1	100
5. MBR Bedroom	11	10	1	110

6. SBR Bedroom	11	10	1	110
7. Other Area (Passage & Staircase Area)	10	10	1	100
Total area - False Ceiling Work				971
Amount Details				
Details	Total Area	Rate	Total Amount	
Total area - Kitchen Box Area - Wood Work - A	113	1500	169500	
Total area - Wardrobe Box Work - Wood Work - B	136	1400	190400	
Total area - Other Box Work - Wood Work - C	302	1200	362400	
Total area - Frame & Panel Work - Wood Work - D	327	750	245250	
Kitchen Accessories - 9' nos	9	5600	50400	
Electrical Work - Wood work	1	42000	42000	
Electrical Work - Staircase Steps Lights	1	18000	18000	
Hydraulic, GT PT, G profile Handle and Doors (Approximate)	1	65000	65000	
HighGloss or Digital or Acrylic laminate Differnce Cost	12	2600	31200	
False Ceiling work (Including Painting Wiring, Lightings)	970	210	203700	
Total Amount			1377850	
Less: Spl. Discount 10 %	10		123000	
Final and Best Offer Price			1254850	
Note: We have quoted the rate considering the nature of work and also the quantam of material utilized.				
Material Specification		Brand		
1. Plywood - 19mm, 16mm & 9mm Thickness - BWP 710 Marine & MR Grade		Suggested Brand - Evergreen, Century and Kitply		
2. Laminate - 1mm & 0.8mm Thickness		Virgo Lam, Greenlam, Merino Lam		
3. Fittings And Accessories		Sleek, Ebco		
4. Adhesive		Fevicol, Araldite		
5. Kitchen Accessories		Sleek - Tandem Baskets		
Kitchen Accessories - 4" Tandem Cutlery Unit 1No, 8" Tandem Plain Basket 2 nos, 10" Tandem Plate Basket 2 nos, 8" SS Oil Pullout 1 no.				

Laminate: Merino or Greenlam or Virgo (Regular Finish) and High Glass Laminates, Pattern finish - additional cost will be charging.

Terms & Conditions

Payment Terms: 60% advance along with order, 30% of payment after delivery of materials, balance 10% of payment handing over the site.

Time Period: From the receipt of advance date to 45 working days.

Taxes: GST will be extra on above prices. (As Discussed)

Civil Work, Plumbing & Electrical Works will be charged Extra.

Any additions and deletions in the work will after the value accordingly.

Final invoice will be made based on the actual scope of work completed.

Any clarification Please free to contact us over mobile.

Expecting your approval to start the work at the earliest.

**For Universal Interiors,
Mobile: 98403 00603**