



UNIVERSAL INTERIORS
TRANSFORM YOUR SPACE

180, 144, Medavakkam Main Rd, Parthasarathy Nagar, Adambakkam, Chennai - 600088
Phone: +91 94444 03550 | Email: universalinterior@gmail.com | Web: www.universalinterio.com | GSTIN: 33AGAPR2552E1ZS

Prepared For:

Mr. Rajesh Kumar
Site: Flat 4B, Ruby Block, Prestige Courtyards,
Sholinganallur, Chennai - 600119
Phone: +91 98401 23456 | Email: rajesh.k@outlook.com

Quotation Details:

Quote Number: UI/2026/QT/084
Date of Issue: 12-Jul-2026
Validity: 30 Days (Until 11-Aug-2026)
Project: 3 BHK Interior Renovation
Designer Coordinator: Mr. Raman Kumar

BUSINESS ESTIMATE & QUOTATION

1. Scope of Work & Concept

This quotation represents the comprehensive design estimate for the interior fit-out work of Mr. Rajesh Kumar's 3 BHK apartment. The proposed scheme focuses on a premium modern-contemporary aesthetic utilizing BWR Marine Plywood for wet zones, Premium Commercial/MR Plywood for dry carpentry, high-gloss acrylic and anti-scratch matte laminates, along with soft-close hardware fittings from Hettich/Ebco.

2. Detailed Space-wise Cost Estimate

S.No.	Space / Area	Item Description & Materials Specification	Dimension s	Qty	UoM	Rate (INR)	Total (INR)
1	Living Room	Entertainment Unit - 18mm BWR Plywood carcass, premium veneer finish panels, customized designer fluted backing. - Soft-close pullout drawers, concealed LED cove light tracks, wire management channels.	8'W x 6'H	1	Nos	45,000	45,000
2	Living Room	Pooja Area Partition - Premium CNC-cut MDF partition panel with teak wood outer frame, hand-polished finish. - Fitted with brass hangers and designer corner brackets.	6'W x 8'H	48	Sq.Ft.	280	13,440
3	Master Bedroom	Sliding Wardrobe - Laminated sliding wardrobe with 18mm BWR plywood structure. - Outer finish: Anti-scratch matte laminate. - Internal layout: Double drawers, hanging rods, safety locker, inner LED sensor lights. - Soft-close sliding channels (Hettich).	8'W x 9'H	72	Sq.Ft.	1,200	86,400
4	Modular Kitchen	L-Shape Premium Kitchen Cabinets - Carcass in 18mm BWR Marine Plywood with internal white laminate finish. - Shutters in high-gloss acrylic finish with edge banding. - Drawers equipped with 4 Tandem boxes, 1 bottle pull-out, and 1 cutlery tray (Hettich). - Custom G-section aluminum handles.	15	Rft.	6,500	97,500	

S.No.	Space / Area	Item Description & Materials Specification	Dimension s	Qty	UoM	Rate (INR)	Total (INR)
5	Entire Flat	Designer False Ceiling - Gypsum board false ceiling (Saint-Gobain) in Living Room and Master Bedroom. - Fitted with metal perimeter channels, joint fillers, and cutouts for LED spotlights/strip lights.	450	Sq.Ft.	110	49,500	
Subtotal Carpentry & False Ceiling Estimate							2,91,840.00
Design & 3D Visualization Consultations Fees (5%)							14,592.00
Project Turnkey Coordination & Site Management Fees (10%)							29,184.00
Material Logistics, Packaging & Site Freight Charges							8,500.00
State & Central Goods and Service Tax (GST 18%)							61,940.40
GRAND ESTIMATE TOTAL (Round Off)							4,06,056.00

3. Payment Milestones Schedule

Milestone	Project Stage Description	Percentage Due	Milestone Value (INR)
Milestone 1	Booking & Advance Deposit (Initiation of design concepts)	10%	40,605.60
Milestone 2	2D/3D Design Sign-off & Client Approvals	40%	1,62,422.40
Milestone 3	Production Stage (Material procurement and carpentry dispatch)	45%	1,82,725.20
Milestone 4	Project Handover & Execution Completion	5%	20,302.80
TOTAL	Project Work Complete	100%	4,06,056.00

4. Terms & Conditions of Work

- Validity:** This estimate is valid for a period of 30 days from the date of issue. Price revisions may apply thereafter.
- Scope Alterations:** Any modifications, additions, or deductions to the scope of work detailed in this quotation will be billed separately via a Work Change Order and must be signed off by the client.
- Warranties:** BWR Carpentry carries a 5-year replacement warranty against manufacturing defects and borer infestation. Hardware accessories carry warranties as specified by their respective manufacturers (Hettich/Ebco).
- Client Scope & Site Readiness:** The client must provide a lockable room at the site for storing materials safely. Electric power and water supply must be made available on site continuously during execution at the client's cost. Civil/masonry, electrical rewiring, and major plumbing work are excluded unless explicitly specified.
- Delay Clause:** In the event of payment delays exceeding 7 business days from a milestone completion, the project completion timeline will be extended proportionally, and a storage fee of 0.5% of material value per week may be charged.

For UNIVERSAL INTERIORS
(Authorized Signatory)

For CLIENT SIGN-OFF
(Mr. Rajesh Kumar)